

SLOVENSKI STANDARD SIST ISO 4310:1997

01-november-1997

Dvigala - Pravila in postopki preskušanja

Cranes -- Test code and procedures

Appareils de levage -- Code et méthodes d'essai PREVIEW

Ta slovenski standard je istoveten z: ISO 4310:1981

 SIST ISO 4310:1997

 https://standards.iteh.ai/catalog/standards/sist/3c611960-190f-4ca5-b837-951e1912190d/sist-iso-4310-1997

 ICS:

 53.020.20
 Dvigala

SIST ISO 4310:1997

en



iTeh STANDARD PREVIEW (standards.iteh.ai)

<u>SIST ISO 4310:1997</u> https://standards.iteh.ai/catalog/standards/sist/3c611960-190f-4ca5-b837-951e1912190d/sist-iso-4310-1997 International Standard



INTERNATIONAL ORGANIZATION FOR STANDARDIZATION® MEX DYHAPODHAR OPFAHUSAUUR ПО СТАНДАРТИЗАЦИИ® ORGANISATION INTERNATIONALE DE NORMALISATION

Cranes — **Test code and procedures**

Appareils de levage - Code et méthodes d'essai

First edition - 1981-05-01

iTeh STANDARD PREVIEW (standards.iteh.ai)

<u>SIST ISO 4310:1997</u> https://standards.iteh.ai/catalog/standards/sist/3c611960-190f-4ca5-b837-951e1912190d/sist-iso-4310-1997

Descriptors : hoists, cranes (hoists), gantry cranes, tests, performance tests, visual inspection, hoisting tests, mechanical tests, static tests, stability tests, testing conditions.

SIST ISO 4310:1997

Foreword

ISO (the International Organization for Standardization) is a worldwide federation of national standards institutes (ISO member bodies). The work of developing International Standards is carried out through ISO technical committees. Every member body interested in a subject for which a technical committee has been set up has the right to be represented on that committee. International organizations, governmental and non-governmental, in liaison with ISO, also take part in the work.

Draft International Standards adopted by the technical committees are circulated to the member bodies for approval before their acceptance as International Standards by the ISO Council.

International Standard ISO 4310 was developed by Technical Committee ISO/TC 96, Cranes, lifting appliances and related equipment, and was circulated to the member bodies in June 1978.

It has been approved by the member bodies of the following countries 110:1997

https://standards.iteh.ai/catalog/standards/sist/3c611960-190f-4ca5-b837-

Australia Austria Bulgaria Czechoslovakia Finland France Germany, F. R. Ireland Israel Korea, Rep. of Mexico Netherlands Norway Philippines Poland Romania 951c19121SouthsAfrica,3 Rep. 967 Spain Switzerland Turkey United Kingdom USSR Yugoslavia

The member bodies of the following countries expressed disapproval of the document on technical grounds :

Belgium India Japan USA

© International Organization for Standardization, 1981 •

Cranes — Test code and procedures

Scope and field of application 1

This International Standard specifies the tests and procedures to be followed in order to verify that a crane conforms to its operational specifications and is capable of lifting rated loads. Where rated loads are governed by stability, a test procedure and test load are specified that permit stability margins to be easily verified.

The following crane types are governed by this International Standard :

- overhead travelling cranes; a)
- travelling bridge cranes; iTeh STANDARD³. Fonformity tests h)
- portal cranes; c)

mobile cranes and crane-excavators; d)

and the following parameters shall be verified : SIST ISO 4310:1997 https://standards.iteh.ai/catalog/standards/sist/3c611960-190f-4ca5-b83/-

- 951e1912190d/sist-iso-4310-1997 distance from axis of rotation to the balance edge; tower cranes;
- f) railway cranes;

e)

- cable cranes; q)
- others to be determined. h)

2 Types of test procedure and number of samples

2.1 Three types of test procedure are to be used to accomplish the aims of this International Standard :

a) testing of cranes for conformity to specifications as set forth in 3.1;

visual inspection as set forth in 3.2; b)

c) load lifting competence testing as set forth in 3.4, 3.5 and 3.6.

2.2 All cranes shall be required to satisfy the test procedures stipulated above; however, in the case of serially manufactured cranes, the sample number of cranes to be tested under a) and c) should be established by mutual agreement between the 'vendor" and the "purchaser".1)

2.3 Cranes which leave the manufacturing factories ready for service shall be tested in these factories prior to delivery; cranes which are mounted or finally assembled at their places of use shall be tested at these places unless other agreements between the vendor and the purchaser are made.

3 **Test procedures**

load lifting height;

When cranes are tested for conformity to specifications, tests (standards. Ishall be performed according to the crane load characteristics,

- hook approaches;
- load lifting speed;
- precision load lowering speed;
- crane travelling speed;
- crab traversing speed;
- slewing speed;
- derricking time;
- telescoping time;
- cycle time (where necessary);
- functioning of limiting devices;

performance of driving medium, for example, motor currents under test load conditions.

In legal terms, the "vendor" and the "purchaser" are understood to be the parties who have signed the contract. The "vendor" is the party supplying the crane. The "purchaser" is the party who receives the crane according to the contract.

3.2 Visual inspection

Visual inspection should include checking for compliance with specifications and/or condition of all vital components such as :

mechanisms, electrical equipment, safety devices, brakes, controls, and lighting and signalling systems;

crane metal structures and their connections, ladders, means of access, cabins, platforms;

all guardings;

hook or other load-handling attachments and their connections:

ropes and their fastenings;

sheave blocks, their pivots and fastening details, and jib linkage elements.

It shall not be inferred that dismantling of any parts is necessary during this inspection but opening of covers which would be required for normal service and inspection purposes shall be included, for example, limit switch covers.

The inspection procedure shall include verification that all certificates required have been submitted and checked. standar

3.3 Load lifting tests

standards.

- static tests;
 - dynamic tests;
 - stability tests (where applicable).

3.3.1 Static tests

3.3.1.1 Static tests are conducted for the purpose of demonstrating the structural competence of the crane and its components.

The test shall be considered to be successful if no crack, permanent deformation, paint flaking or damage which affects the function and safety of the crane is visible and no connection has loosened or been damaged.

3.3.1.2 Static tests shall be performed separately for each hoisting mechanism and for concurrent operation of hoisting mechanism, if permitted by the crane specification, in such positions and configurations as will impose maximum rope loads, maximum bending moments and/or maximum axial forces, as applicable, in the major crane components.

The test load, built up progressively, shall be lifted 100 to 200 mm from the ground and suspended for a period necessary for the test but not less than 10 min unless a higher value is required.

3.3.1.3 The test load shall be 1.25 P for all cranes unless a higher value is required by national regulations or specified in the purchase contract, where P is defined as follows :

a) for mobile cranes : the load on the hoisting mechanism, including the weight of the payload and the weight of the hook assembly and rigging attachments;

b) for other cranes : the rated capacity for the equipment as specified by the manufacturer. Rated capacity does not include any lifting attachment which is a permanent part of the crane in its working condition.

3.3.2 Dynamic tests

3.3.2.1 Dynamic tests are conducted primarily for the purpose of verifying the functioning of crane mechanisms and brakes.

The test shall be considered to be successful if the components concerned have been found to perform their functions and if visual inspection subsequent to the test reveals no damage to the mechanisms or structural components, and no connection has loosened or been damaged.

During performance of the test, the crane shall be controlled according to the rules specified in the operating manual, and care must be taken to limit accelerations, decelerations, and speeds to those appropriate to normal crane operation.

SIST ISO 33(2)297 Dynamic tests shall be performed separately for each iteh ai/catalog/standacrasetmotion or if stated in the specifications of the crane, for Load lifting competence testing shall include the following 2190d/sist-so-4310-199 as will impose maximum loading on the mechanism(s). Tests shall include repeated starting and stopping for each motion throughout the range of the motion and shall continue for 1 h minimum under consideration of the duty cycle. The tests shall include a mid-air start with the test load suspended. No back running should occur with the test load under these circumstances.

> **3.3.2.3** The test load shall be 1,1 P unless a higher value is re quired.

3.3.3 Stability tests

The purpose of the stability test is to check crane 3.3.3.1 stability. The test shall be considered to be successful if no crane tipping occurs when the crane's hook is statically loaded.

3.3.3.2 Stability test loads for mobile cranes shall be determined according to the formula :

$$1,25 P + 0,1 F_i$$
 ... (1)

where F_i (F_1 or F_2) is the jib weight G or fly jib weight g reduced to the head of the jib or that of the fly jib.

Where jib weight G is very high and the fly-jib is designed for relatively light loads, the stability test shall not be performed with the test load, according to formula (1), lifted on the head of the fly-jib. Such stability requirements shall be verified by calculation.

NOTE -1,25 P may alter where a higher value is required.

The figure shows the side elevation for a typical crane giving the designations of the parameters to be considered.

L and l — lengths of jib and fly jib (for telescopic jibs, L will relate to the jib length under consideration);

(X, Y) and (x, y) – co-ordinates of centres of gravity for jib and fly jib;

j and k – radii for jib and fly jib;

m and n – radii of centres of gravity for jib and fly jib.

$$F_i$$
 is calculated as follows

$$F_i = \frac{m G + g (j + n)}{j + k} \qquad \dots (2)$$

For cranes equipped only with a jib, k = n = g = 0 and

$$F_1 = \frac{m}{j}G$$



Figure - Designation of parameters for determination of stability test loads

For cranes equipped with a jib and a fly jib, if the load is lifted on jib head, k = 0 and

$$F_1 = \frac{m G + g (j + n)}{i}$$

If the load is lifted on fly jib head,

$$F_2 = \frac{m \ G + g \ (j + n)}{j + k}$$

NOTE - Values of P_i , G_i , g and co-ordinates of centres of gravity (X, Y) and (x, y) shall be specified in the crane documentation for each of the lengths L and l.

3.3.3.3 For cranes other than mobile cranes, special stability tests may not be required.

3.3.3.4 The tests shall be carried out in those positions or configurations within the specified working area for which stability is at a minimum. If different loads are specified for different positions or working areas, tests shall be carried out to check the stability for a selection of those conditions.

3.4 Test report

On completion of the tests outlined in 2.1, a report shall be prepared listing the conclusions and findings of the tests. The ar report shall identify the crane tested, and shall give the date and location of the tests and the name of the test supervisor. It shall be specific as to the loads, positions, configurations, prost IS(cedures and findings in each case https://standards.iteh.ai/catalog/standthesvendor(specifies)otherwise.837-

For cranes that are subject to the requirements of 2.1b) only, an abbreviated form of report may be used. The identity of the crane, date and location of inspection, name of inspector and the findings for each item inspected shall be included in an abbreviated report.

Test conditions 4

4.1 For the purpose of testing, the crane shall be equipped with working equipment suitable for operation with the rated load in accordance with specifications.

4.2 Cranes travelling on rail tracks shall be tested on rails manufactured and laid in conformity with the crane specifications.

4.3 When testing cranes on pneumatic tyres or crawler equipment, the appliance shall be placed on a firm level surface (within \pm 0,5 %).

4.4 At the time of test, wind speed shall not exceed 8,3 m/s (30 km/h), but this should not be construed as requiring that the crane be oriented so as to receive the most unfavourable effect of wind unless otherwise specified in the purchase contract.

4.5 When testing pneumatic tyred equipment while operating on tyres, the tyres shall be inflated to within \pm 3 % of the pressure stipulated by the manufacturer, and all wheels shall be in the ahead position.

NOTE - Supporting conditions for the tyres are to align with manufacturers requirements.

4.6 For conducting tests of cranes with outriggers in the "on outriggers" condition, the crane shall be level within \pm 0,5 %.

4.6.1 When outriggers are used in the course of testing pneumatic tyred cranes, the crane shall be raised by the outriggers so as to provide clearance between the ground and all the wheels of to relieve all wheels of the weight of the crane unless

2190d/sist-iso-4310-1997

4.6.2 When outriggers are used in the course of testing crawler cranes, the crane shall be installed so as to provide firm bearing of the outriggers on the supporting surface.

4.6.3 Other cranes shall be set up as specified by national regulations or contract.

4.7 The fuel tank shall be between 1/3 and 2/3 full. Coolant, lubricating oil and hydraulic fluids shall be at operating levels specified by the vendor.