

Designation: C969 - 17 C969 - 19

Standard Practice for Infiltration and Exfiltration Acceptance Testing of Installed Precast Concrete Pipe Sewer Lines¹

This standard is issued under the fixed designation C969; the number immediately following the designation indicates the year of original adoption or, in the case of revision, the year of last revision. A number in parentheses indicates the year of last reapproval. A superscript epsilon (ε) indicates an editorial change since the last revision or reapproval.

This standard has been approved for use by agencies of the U.S. Department of Defense.

1. Scope

- 1.1 This practice covers procedures for testing installed precast concrete pipe sewer lines using either water infiltration or exfiltration acceptance limits to demonstrate the integrity of the installed materials and construction procedure.
 - 1.2 This practice is the inch-pound companion to Practice C969M; therefore, no SI equivalents are presented in the practice.

Note 1—The owner shall specify the following: who will conduct, observe, and furnish labor, furnish material and measuring devices, and pay for the tests; who is responsible for determining local groundwater conditions; and which test is to be conducted, that is, an infiltration test or an exfiltration test

Note 2—The user of this practice is advised that test criteria presented in this practice are similar to those in general use. Pipe, 24-in. diameter or larger, may be accepted by visual inspection when testing for infiltration.

- 1.3 This standard does not purport to address all of the safety concerns, if any, associated with its use. It is the responsibility of the user of this standard to establish appropriate safety and health practices and determine the applicability of regulatory limitations prior to use.
- 1.4 This international standard was developed in accordance with internationally recognized principles on standardization established in the Decision on Principles for the Development of International Standards, Guides and Recommendations issued by the World Trade Organization Technical Barriers to Trade (TBT) Committee.

2. Referenced Documents

2.1 ASTM Standards:²

C822 Terminology Relating to Concrete Pipe and Related Products

- 3. Terminology 155/astm-c969-19
 - 3.1 Definitions—For definitions of terms relating to concrete pipe, see Terminology C822.

4. Summary of Practice

- 4.1 Determine the groundwater conditions surrounding the section of sewer to be tested and select the type of test to be conducted.
- 4.2 For the infiltration test, the amount of water leaking into the sewer line is measured, and the rate of infiltration is determined. If the rate is less than or equal to the allowable limit, the section of sewer tested is acceptable.
- 4.3 For the exfiltration test, the sewer line is filled with water to the specified test head and the rate of water loss is determined. If the rate is less than or equal to the allowable limit, the section of sewer tested is acceptable.

5. Significance and Use

5.1 This is not a routine test. The values recorded are applicable only to the sewer being tested and at the time of testing.

¹ This practice is under the jurisdiction of ASTM Committee C13 on Concrete Pipe and is the direct responsibility of Subcommittee C13.09 on Methods of Test. Current edition approved April 15, 2017Jan. 1, 2019. Published May 2017January 2019. Originally approved in 1982. Last previous edition approved in 20092017 as C969 – 02C969 – 17.(2009). DOI: 10.1520/C0969-17.10.1520/C0969-19.

² For referenced ASTM standards, visit the ASTM website, www.astm.org, or contact ASTM Customer Service at service@astm.org. For *Annual Book of ASTM Standards* volume information, refer to the standard's Document Summary page on the ASTM website.



6. Preparation of the Sewer Line

- 6.1 The sewer shall should be free of debris prior to testing.
- 6.2 The manholes, the ends of the branches, laterals, wyes and stubs to be included in the test shall be plugged. All plugs shall be secured to prevent leakage blowout due to testing pressure.

7. Procedure

- 7.1 *Infiltration Testing:*
- 7.1.1 Conduct testing from manhole to manhole or between more than two manholes. The length of main tested shall not exceed 700 ft.
- 7.1.2 Stop all dewatering operations and allow the groundwater to return to its normal level. Infiltration testing shall not be used unless the groundwater level is at least 2 ft above the crown of the pipe for the entire length of the test section.
 - 7.1.3 Plug all pipe outlets discharging into the upstream manhole.
 - 7.1.4 Measure the groundwater elevation and determine the average head over the test section.
- 7.1.5 Measure infiltration leakage at the outlet of the test section. Because leakage allowances are small, measurements are best made by either timing the filling of a small container of known volume, or by directing flow into a container for a specified time and measuring the content, or by using small weirs.
- 7.1.6 If the measured rate of leakage is less than or equal to the allowable leakage in accordance with 8.1, the section of sewer tested is acceptable.
 - 7.1.7 If the test section fails, it is not prohibited that it be repaired and retested in accordance with this practice.
 - 7.2 Exfiltration Testing:
- 7.2.1 Conduct testing from manhole to manhole or between more than two manholes. The length of main tested shall not exceed 700 ft.
- 7.2.2 Determine the groundwater elevation at both ends of the test section. If the groundwater level is less than 2 ft above the crown of the pipe measured from the highest elevation of the sewer, the exfiltration test shall be used.
 - 7.2.3 Plug all pipe outlets discharging into the upstream manhole and the test section outlet. Fill the sewer line with water.
- 7.2.4 At the upstream manhole the test head shall be established as minimum of 2 ft above the crown of the pipe, or at least 2 ft above existing groundwater, whichever is higher.
- 7.2.5 Allow the pipe to remain saturated for a period long enough to allow water absorption in the pipe, a minimum of 4 h and up to a maximum of 72 h. After the absorption period, refill the pipe to the required test head.
- 7.2.6 Measure the leakage loss over a timed test period. The minimum test period shall be 15 min and the maximum shall not exceed 24 h.
- 7.2.7 If the measured rate of leakage is less than or equal to the allowable leakage in accordance with 8.2, the section of sewer tested is acceptable.

 ASTM C969-19
- 7.2.8 If the test section fails, it is not prohibited that it be repaired and retested in accordance with this practice. The groundwater elevation shall be redetermined prior to a second test and the test head adjusted, if necessary, in accordance with 7.2.4.

8. Leakage Criteria

- 8.1 *Infiltration Testing:*
- 8.1.1 For infiltration testing, the allowable leakage limit including manholes is 200 gal/(in. of internal diameter) (mile of sewer) (24 h) when the average head on the test section is 6 ft or less.
- Note 3—The average head on the test section is the head above the crown of the pipe at the upstream manhole plus the head above the crown of the pipe at the downstream manhole divided by two.
- 8.1.2 When the average groundwater head on the test section is greater than 6 ft, the allowable leakage shall be increased in proportion to the ratio of the square root of the average groundwater head to the square root of the base head of 6 ft.
- 8.1.3 Manholes shall be tested separately and independently or with the pipeline with the allowance of 0.1 gal/(ft of diameter) (ft of head) (h). If building or house leads are connected to the main line being tested, allowance shall be made for permissible leakage in such leads.
 - 8.2 Exfiltration Testing:
- 8.2.1 For exfiltration testing the allowable leakage limit including manholes is 200 gal/(in. of internal diameter) (mile of sewer) (24 h) when the average head on the test section is 36 ft or less.
- 8.2.2 When the average head on the test section is greater than 6 ft, the allowable leakage shall be multiplied by the ratio of the square root of the average test head and the square root of the base head of 6 ft.
- 8.2.3 Manholes shall be tested separately and independently or with the pipeline with an allowance of 0.1 gal/(ft of diameter) (ft of head) (h).

9. Calculation

9.1 Sample calculations are presented in Appendix X1.