![SIST logo]

SLOVENSKI STANDARD
SIST EN 12838:2003

01-januar-2003

BUdYˆ^UjY¨]b˙cdfYa U˙nU˙i hY_c]b^Yb]˙nYa Yˆg_]˙d`]b˙!˙DfYg_i ýUb^Yˆi glfYnbcgh]˙!˙G]glYa]˙nU˙jncf Yb^Y

Installations and equipment for liquefied natural gas - Suitability testing of LNG sampling systems

Anlagen und Ausrüstung für Flüssigerdgas - Eignungsprüfung von Flüssigerdgas-Probenahmesystemen

Installations et équipements relatifs au gaz naturel liquéfié - Essais d'aptitude a l'emploi des systemes d'échantillonnage du GNL

Ta slovenski standard je istoveten z: **EN 12838:2000**

ICS:

75.200	U]¦^{ æÁ æÁ|æåã ^}b }æc^Ei æç,ã@Á¦[ãç[å[çÁ§ :^{ ^|b\^*æÁ|ã æ	Petroleum products and natural gas handling equipment

SIST EN 12838:2003 **en**

2003-01.Slovenski inštitut za standardizacijo. Razmnoževanje celote ali delov tega standarda ni dovoljeno.

iTeh STANDARD PREVIEW
(standards.iteh.ai)

EUROPEAN STANDARD

NORME EUROPÉENNE

EUROPÄISCHE NORM

EN 12838

January 2000

ICS 75.200

English version

Installations and equipment for liquefied natural gas - Suitability testing of LNG sampling systems

Installations et équipements relatifs au gaz naturel liquéfié - Essais d'aptitude à l'emploi des systèmes d'échantillonnage du GNL

Anlagen und Ausrüstung für Flüssigerdgas - Eignungsprüfung von Flüssigerdgas-Probenahmesystemen

This European Standard was approved by CEN on 3 December 1999.

CEN members are bound to comply with the CEN/CENELEC Internal Regulations which stipulate the conditions for giving this European Standard the status of a national standard without any alteration. Up-to-date lists and bibliographical references concerning such national standards may be obtained on application to the Central Secretariat or to any CEN member.

This European Standard exists in three official versions (English, French, German). A version in any other language made by translation under the responsibility of a CEN member into its own language and notified to the Central Secretariat has the same status as the official versions.

CEN members are the national standards bodies of Austria, Belgium, Czech Republic, Denmark, Finland, France, Germany, Greece, Iceland, Ireland, Italy, Luxembourg, Netherlands, Norway, Portugal, Spain, Sweden, Switzerland and United Kingdom.

EUROPEAN COMMITTEE FOR STANDARDIZATION
COMITÉ EUROPÉEN DE NORMALISATION
EUROPÄISCHES KOMITEE FÜR NORMUNG

Central Secretariat: rue de Stassart, 36   B-1050 Brussels

Ref. No. EN 12838:2000 E

Page 2
EN 12838:2000

Contents

iTeh STANDARD PREVIEW
(standards.iteh.ai)

Page 4
EN 12838:2000

Foreword

This European Standard has been prepared by Technical Committee CEN/TC 282 "Installation and equipment for LNG", the secretariat of which is held by AFNOR.

This European Standard shall be given the status of a national standard, either by publication of an identical text or by endorsement, at the latest by July 2000, and conflicting national standards shall be withdrawn at the latest by July 2000.

According to the CEN/CENELEC Internal Regulations, the national standards organizations of the following countries are bound to implement this European Standard: Austria, Belgium, Czech Republic, Denmark, Finland, France, Germany, Greece, Iceland, Ireland, Italy, Luxembourg, Netherlands, Norway, Portugal, Spain, Sweden, Switzerland and the United Kingdom.

1 Scope

This standard specifies the tests to be carried out in order to assess the suitability of LNG sampling systems designed to determine the composition of Liquefied Natural Gas, in combination with an analytical device such as a chromatograph.

2 Normative references

This European Standard incorporates by dated or undated reference, provisions from other publications. These normative references are cited at the appropriate places in the text and the publications are listed hereafter. For dated references, subsequent amendments to or revisions of any of these publications apply to this European Standard only when incorporated in it by amendment or revision. For undated references the latest edition of the publication referred to applies.

EN 1160, *Installations and equipment for liquefied natural gas - General characteristics of liquefied natural gas.*

ISO 2854, *Statistical interpretation of data - Techniques of estimation and tests relating to means and variances.*

ISO 6568, *Natural gas - Simple analysis by gas chromatography.*

ISO 6578, *Refrigerated hydrocarbon liquids - Static measurement - Calculation procedure.*

ISO 6976, *Natural gas - Calculation of calorific values, density, relative density and Wobbe index from composition.*

ISO 8943, *Refrigerated light hydrocarbon fluids - Sampling of liquefied natural gas - Continuous method.*

3 Terms and definitions

For the purposes of this European Standard, the following definitions in addition to those given in EN 1160, apply :

3.1
liquefied natural gas (LNG)
see EN 1160

3.2
transfer line
pipe through which LNG is transferred

3.3
sampling bomb
small capacity container filled with vaporized LNG and used to determine the composition by means of a chromatograph

3.4
continuous sampling
process for continuously collecting Liquefied Natural Gas from the transfer line, which is subsequently vaporized and stored in a gasholder

3.5
discontinuous sampling
process for continuously collecting Liquefied Natural Gas from the transfer line; the liquefied natural gas is subsequently vaporized and either analysed by chromatography at regular intervals, or sampled in sampling bombs at regular intervals

3.6
reference gas
gas against which the gas sampled, by means of the tested sampling system, is compared

Page 6
EN 12838:2000

3.7
regression equation of the reference gas
relationship of a physical property with time, calculated via a polynomial function of order 5

4 Description of a continuous LNG sampling system

The continuous LNG sampling system to be tested for suitability prior to installation on a transfer line, shall be designed in accordance with the requirements of ISO 8943 standard. It is characterized by the use of a small capacity gasholder within which a sample of vaporized LNG, representative of the stock, is stored throughout the entire transfer operation.

Once the transfer operation is completed, sampling bombs are filled with the gas stored in the gasholder. The LNG composition is then determined by chromatographic analysis of the gas contained in the sampling bombs for subsequent determination of the physical properties of the stock (LNG density, gas density and calorific value).

Annex A presents a diagram of a continuous LNG sampling system.

5 Description of a discontinuous LNG sampling system

A discontinuous sampling system supplies a continuous flow of natural gas derived from LNG vaporization, which is transferred via a sampling line to a chromatograph for analysis, at regular intervals, of the composition of the LNG conveyed in the transfer line. In the absence of a sampling line, sampling bombs may be filled at regular intervals for subsequent chromatographic analysis of the contents.

Once the transfer operation is completed, the physical properties of the LNG are then deduced via the arithmetic mean of the properties derived from the respective analyses.

Annex B presents a diagram of two discontinuous LNG sampling systems.

6 Characteristics of the test rig

6.1 Description of the test rig

The accuracy of an LNG sampling system shall be determined by comparing physical properties such as density and gross calorific value derived from chromatographic analyses with the same properties calculated on the basis of the composition of the gas sampled following supercritical regasification of the LNG. The regasified LNG, hereafter designated as "reference gas", shall serve as a reference to assess the accuracy of the tested sampling systems.

NOTE   The supercritical regasification process eliminates any risk of fractionated vaporization during LNG transformation into natural gas. The composition of the resulting reference gas is thus free from fluctuation during regasification. Annex C describes the thermodynamic conditions for LNG transformation into natural gas for various gas compositions.

The test rig shall be composed of the following :

a)   a regasification unit, consisting of one LNG storage tank, one primary pump, one high pressure pump and one vaporizer ;

b)   a low pressure test loop containing the tested LNG sampling system ;

c)   a sampling line for transfer of the reference gas from the sampling point located after the vaporizer towards a chromatograph ;

d)   in the case of a discontinuous sampling system, a sampling line between the sampling system and the chromatograph.

Annex D specifies the test rig to be used.

NOTE   All precautions should be taken to prevent any partial condensation of the reference gas prior to analysis.

6.2 Measurement required

6.2.1 Measurement required to evaluate the test rig

In order to evaluate the test rig, the following quantities shall be measured and recorded :

a) LNG pressure and temperature in the vicinity of the tested sampling system ;

b) gas pressure at the outlet of the high pressure vaporizer ;

c) flow rate of the high pressure vaporizer ;

d) natural gas temperature in the vicinity of the sampling point of reference gas ;

e) composition of reference gas by chromatographic analysis in compliance with ISO 6568.

Annex E specifies the measuring equipment to be used.

6.2.2 Measurement required to evaluate a continuous LNG sampling system

The following quantities shall be measured and recorded in order to evaluate a continuous LNG sampling system :

a) temperature and flow rate of the gas leaving the sampling vaporizer ;

b) pressure and flow rate of the gas during filling of the gasholder ;

c) pressure and flow rate of the gas during filling of the sampling bombs ;

d) composition of the gas contained in the sampling bombs by means of the same chromatograph as previously used to analyze the composition of the reference gas.

Annex F specifies the measuring equipment to be used.

6.2.3 Means required to evaluate a discontinuous LNG sampling system

The following quantities shall be measured and recorded in order to evaluate a discontinuous LNG sampling system :

a) temperature and pressure of the gas leaving the sampling vaporizer ;

b) flow rate of the gas transferred via the sampling line ;

c) composition of the gas vaporized in the LNG sampling system by means of the same chromatograph as previously used to analyze the composition of the reference gas.

Annex G specifies the measuring equipment to be used.

7 Suitability tests

7.1 General requirements of test performance

The suitability testing of an LNG sampling system shall be regarded as valid only if the following requirements are met :

a) the number of analyses performed to determine the composition of the reference gas shall be at least 40 ;

b) when testing a continuous LNG sampling system, the duration of gasholder filling time shall be equal to the time required to determine the composition of the reference gas; in addition, the number of analyses performed to determine the composition of the gas contained in each sampling bomb shall be at least 6 ;

c) when testing a discontinuous LNG sampling system, the number of analyses on the gas flowing from the system shall be identical to the number of analyses performed on the reference gas; such analyses shall be performed alternatively on collected on LNG samples and reference gas samples collected alternately.

7.2 Operating procedure

The test shall be performed in accordance with the following operating procedure :

a) start up the regasification unit ;

b) start up the tested LNG sampling system as soon as the regasification unit reaches a stabilized supercritical state ;

c) sample the reference gas and the LNG in accordance with the following procedure :

1) measurement and recording of the physical properties (pressure, temperature, flow rate) characterizing the flow in the various LNG and natural gas lines ;

2) determination of the reference gas composition ;

3) when testing a discontinuous LNG sampling system, chromatographic analyses of the LNG samples ;

4) when testing a continuous LNG sampling system, filling of the gasholder ;

d) shutdown the regasification unit ;

e) when testing a continuous LNG sampling system, fill the sampling bombs and subsequently determine the composition of the gas samples.

7.3 Calculation of suitability criteria for the tested sampling system

7.3.1 General principles

The suitability of the LNG sampling system shall be assessed by calculating the accuracy of the values of the physical properties (for example gross calorific value, gas density and LNG density) derived from the chromatographic analyses of the gas performed with the chromatograph associated to the tested sampling system.

The gross calorific value (Hs) and gas density (ρ_{NG}), shall be calculated in accordance with ISO 6976. The LNG density (ρ_{LNG}) shall be calculated in accordance with ISO 6578.

7.3.2 Method of calculation of the accuracy of the test rig

During the LNG sampling system test, the relationship with time of the physical property referenced as X (Hs, ρ_{LNG} or ρ_{NG}) and derived from the chromatographic analyses on the reference gas shall be determined by calculating the constants of the regression equation of the reference gas according to the least squares method.

The accuracy of the test rig shall be determined by calculating the following values :

a) the random error $E_{R,X_{Ref}}$ affected to each value X_{Ref} derived for one gas analysis ;

b) the random error $E_{R,\overline{X_{Ref}}}$ affected to the mean values $\overline{X_{Ref}}$ of the reference gas.

Annex H specifies the calculation method required to determine the accuracy of the test rig.

The test rig is judged suitable if it conforms to the following requirements :

$$E_{R,\overline{H_{S_{Ref}}}} < 2{,}0 \text{ kJ / kg}, \quad E_{R,\overline{\rho_{LNG_{Ref}}}} < 12 \times 10^{-3} \text{ kg/m}^3, \quad E_{R,\overline{\rho_{NG_{Ref}}}} < 4 \times 10^{-5} \text{ kg/m}^3.$$

7.3.3 Method of calculation of the accuracy of a continuous LNG sampling system

The accuracy of the tested sampling system shall be determined by calculating the following values for each individual gas analysis performed with the tested system :

a) deviation ΔX_i between the considered physical property, derived from each analysis and referenced as i, for the gas contained in the sampling bombs, and the mean value of the same property derived from analyses of the reference gas ;

b) random error $E_{R,X}$ of the physical property X ;

c) systematic error $E_{S,X}$ of the physical property, the statistical significance of which shall be checked in accordance with ISO 2854.

Annex J specifies the calculation method required to determine the accuracy for the tested sampling system.

7.3.4 Method of calculation of the accuracy of a discontinuous LNG sampling system

All calculations shall take into account the time corresponding to the instant when the gas sample analyzed passes the sampling point.

The accuracy of the tested sampling system shall be determined by calculating the following values for each individual gas analysis (referenced as i) performed with the tested system :

a) deviation ΔX_i between the value of the considered physical property and the value derived from the regression equation of the reference gas at the instant of collection of the gas sample at the sampling point of the tested system ;

b) random error $E_{R,X}$ of the physical property X ;

c) systematic error $E_{S,X}$ of the physical property, the statistical significance of which shall be checked in accordance with ISO 2854.

Annex K specifies the calculation method required to determine the accuracy of the tested sampling system.

8 Suitability criteria for the LNG sampling system

The tested sampling system is judged suitable if it conforms to the requirements of either of the accuracy classes defined in Table 1.

Table 1 — Suitability criteria for a tested sampling system

Class	Physical property	continuous		discontinuous	
		Maximal random error	Maximal systematic error (absolute value)	Maximal random error	Maximal systematic error (absolute value)
	Hs in kJ/kg	9,0		54	
A	ρ_{NG} in kg/m³	$3,0 \times 10^{-4}$	Not significant	18×10^{-4}	Not significant
	ρ_{LNG} in kg/m³	0,15		0,90	
	Hs in kJ/kg	18	11	$1,1 \times 10^{2}$	11
B	ρ_{NG} in kg/m³	$6,0 \times 10^{-4}$	$5,0 \times 10^{-4}$	36×10^{-4}	$5,0 \times 10^{-4}$
	ρ_{LNG} in kg/m³	0,30	0,20	1,8	0,20

9 Test report

The results from the tests of the LNG sampling system shall be recorded in a report containing the following data :

a) name of testing body ;

b) date of test ;

c) name of the manufacturer of the tested sampling system ;

d) a detailed description of the tested LNG sampling system by means of a technical data sheet including in particular pressure, temperature and flow rate of the various components at the nominal operating conditions ;

e) technical data sheets of all measuring and recording devices as well as the last revision of their calibration sheet, if applicable ;

f) the detailed procedure followed during the calibration test in terms of preparation, start-up and utilization of the tested sampling system ;

g) measurements taken during the operation of the test rig and during the test of the sampling system (see 6.2) ;

h) measurements of the reference gas, composition ;

i) measurements of the composition of the gas generated by the tested sampling system ;

j) values of the accuracy of the test rig ;

k) values of the random and systematic errors on the following physical properties :

   1) gross calorific value (H_s) ;

   2) density of gas (ρ_{NG}) ;

   3) density of LNG (ρ_{LNG}) ;

l) the accuracy class of the tested sampling system.