



Designation: C 1244 – 02<sup>e1</sup>

## Standard Test Method for Concrete Sewer Manholes by the Negative Air Pressure (Vacuum) Test Prior to Backfill<sup>1</sup>

This standard is issued under the fixed designation C 1244; the number immediately following the designation indicates the year of original adoption or, in the case of revision, the year of last revision. A number in parentheses indicates the year of last reapproval. A superscript epsilon ( $\epsilon$ ) indicates an editorial change since the last revision or reapproval.

<sup>e1</sup> NOTE—Permissive language and a value in Table 1 were editorially corrected in August 2004.

### 1. Scope

1.1 This test method covers procedures for testing precast concrete manhole sections when using the vacuum test method to demonstrate the integrity of the installed materials and the construction procedures. This test method is used for testing concrete manhole sections utilizing mortar, mastic, or gasketed joints.

1.2 This test method is intended to be used as a preliminary test to enable the installer to demonstrate the condition of the concrete manholes prior to backfill.

1.3 *This standard does not purport to address all of the safety problems, if any, associated with its use. It is the responsibility of the user of this standard to establish appropriate safety and health practices and determine the applicability of regulatory limitations prior to use.*

1.4 This test method is the companion to metric Test Method C 1244M; therefore, no SI equivalents are shown in this test method.

NOTE 1—Vacuum test criteria presented in this test method are similar to those in general use. The test and criteria have been widely and successfully used in testing manholes.

NOTE 2—The user of this test method is advised that no correlation has been found between vacuum (air) and hydrostatic tests.

### 2. Referenced Documents

#### 2.1 ASTM Standards:<sup>2</sup>

C 822 Terminology Relating to Concrete Pipe and Related Products

C 924 Practice for Testing Concrete Pipe Sewer Lines by

Low-Pressure Air Test Method  
C 969 Practice for Infiltration and Exfiltration Acceptance  
Testing of Installed Precast Concrete Pipe Sewer Lines

### 3. Terminology

3.1 For definitions of terms relating to manholes, see Terminology C 822.

### 4. Summary of Practice

4.1 All lift holes and any pipes entering the manhole are to be plugged. A vacuum will be drawn and the vacuum drop over a specified time period is used to determine the acceptability of the manhole.

### 5. Significance and Use

5.1 This is not a routine test. The values recorded are applicable only to the manhole being tested and at the time of testing.

### 6. Preparation of the Manhole

6.1 All lift holes shall be plugged.

6.2 All pipes entering the manhole shall be temporarily plugged, taking care to securely brace the pipes and plugs to prevent them from being drawn into the manhole.

### 7. Procedure

7.1 The test head shall be placed at the top of the manhole in accordance with the manufacturer's recommendations.

7.2 A vacuum of 10 in. Hg shall be drawn on the manhole, the valve on the vacuum line of the test head closed, and the vacuum pump shut off. The time shall be measured for the vacuum to drop to 9 in. Hg.

7.3 The manhole is acceptable if the time for the vacuum reading to drop from 10 in. Hg to 9 in. Hg meets or exceeds the values indicated in Table 1.

7.4 If the manhole fails the initial test, the manhole shall be repaired by an approved method until a satisfactory test is obtained.

<sup>1</sup> This practice is under the jurisdiction of ASTM Committee C13 on Concrete Pipe and is the direct responsibility of Subcommittee C13.06 on Manholes and Specials.

Current edition approved April 10, 2002. Published June 2002. Originally published as C 1244 – 93. Last previous edition C 1244 – 93(2000).

<sup>2</sup> For referenced ASTM standards, visit the ASTM website, www.astm.org, or contact ASTM Customer Service at service@astm.org. For *Annual Book of ASTM Standards* volume information, refer to the standard's Document Summary page on the ASTM website.