# PUBLICLY AVAILABLE SPECIFICATION



First edition 2010-06-01

### Ships and marine technology — Measures to prevent asbestos emission and exposure during ship recycling

Navire et technologie maritime — Mesures préventives concernant l'émission et l'exposition à l'amiante lors du recyclage des navires

## iTeh STANDARD PREVIEW (standards.iteh.ai)

ISO/PAS 30007:2010 https://standards.iteh.ai/catalog/standards/sist/c36cd274-7408-4fc8-a6b6-29d8e2c37dff/iso-pas-30007-2010



Reference number ISO/PAS 30007:2010(E)

#### PDF disclaimer

This PDF file may contain embedded typefaces. In accordance with Adobe's licensing policy, this file may be printed or viewed but shall not be edited unless the typefaces which are embedded are licensed to and installed on the computer performing the editing. In downloading this file, parties accept therein the responsibility of not infringing Adobe's licensing policy. The ISO Central Secretariat accepts no liability in this area.

Adobe is a trademark of Adobe Systems Incorporated.

Details of the software products used to create this PDF file can be found in the General Info relative to the file; the PDF-creation parameters were optimized for printing. Every care has been taken to ensure that the file is suitable for use by ISO member bodies. In the unlikely event that a problem relating to it is found, please inform the Central Secretariat at the address given below.

## iTeh STANDARD PREVIEW (standards.iteh.ai)

ISO/PAS 30007:2010 https://standards.iteh.ai/catalog/standards/sist/c36cd274-7408-4fc8-a6b6-29d8e2c37dff/iso-pas-30007-2010



#### **COPYRIGHT PROTECTED DOCUMENT**

#### © ISO 2010

All rights reserved. Unless otherwise specified, no part of this publication may be reproduced or utilized in any form or by any means, electronic or mechanical, including photocopying and microfilm, without permission in writing from either ISO at the address below or ISO's member body in the country of the requester.

ISO copyright office Case postale 56 • CH-1211 Geneva 20 Tel. + 41 22 749 01 11 Fax + 41 22 749 09 47 E-mail copyright@iso.org Web www.iso.org Published in Switzerland

### Contents

Forewo	ord	V
1	Scope	1
2	Terms and definitions	1
3	Work categorization (grade) to minimize asbestos emissions and exposure during ship recycling	2
4	Preliminary check for asbestos-containing materials	3
5 5.1	Planning removal of ACM	
5.2	Operational overview	3
5.3 5.4	Organizational chart for managing asbestos removal Operating schedule	
5.5 5.6	Removal written plan	3
5.6 5.7	Asbestos monitoring plan Waste disposal plan	
6	Work procedures for each work grade	4
6.1 6.2	General	4 4
6.3	Work grade 2	0
6.4 6.5	Work Grade 3 1   Considerations for asbestos insulation piping 1	
Bibliog	raphy	

### Foreword

ISO (the International Organization for Standardization) is a worldwide federation of national standards bodies (ISO member bodies). The work of preparing International Standards is normally carried out through ISO technical committees. Each member body interested in a subject for which a technical committee has been established has the right to be represented on that committee. International organizations, governmental and non-governmental, in liaison with ISO, also take part in the work. ISO collaborates closely with the International Electrotechnical Commission (IEC) on all matters of electrotechnical standardization.

International Standards are drafted in accordance with the rules given in the ISO/IEC Directives, Part 2.

The main task of technical committees is to prepare International Standards. Draft International Standards adopted by the technical committees are circulated to the member bodies for voting. Publication as an International Standard requires approval by at least 75 % of the member bodies casting a vote.

In other circumstances, particularly when there is an urgent market requirement for such documents, a technical committee may decide to publish other types of document:

- an ISO Publicly Available Specification (ISO/PAS) represents an agreement between technical experts in an ISO working group and is accepted for publication if it is approved by more than 50 % of the members of the parent committee casting avote; TANDARD PREVIEW
- an ISO Technical Specification (ISO/TS) represents an agreement between the members of a technical committee and is accepted for publication if it is approved by 2/3 of the members of the committee casting a vote.

#### ISO/PAS 30007:2010

An ISO/PAS or ISO/TS is reviewed after three years in order to decide whether it will be confirmed for a further three years, revised to become an International Standard, or withdrawn. If the ISO/PAS or ISO/TS is confirmed, it is reviewed again after a further three years, at which time it must either be transformed into an International Standard or be withdrawn.

Attention is drawn to the possibility that some of the elements of this document may be the subject of patent rights. ISO shall not be held responsible for identifying any or all such patent rights.

ISO/PAS 30007 was prepared by Technical Committee ISO/TC 8, Ships and marine technology.

### Ships and marine technology — Measures to prevent asbestos emission and exposure during ship recycling

#### 1 Scope

This Publicly Available Specification provides effective methods for minimizing the dangers of asbestos during ship recycling, reducing both the release of asbestos into the environment and worker exposure to asbestos. It helps ship recyclers to fulfil the requirements of The Hong Kong International Convention for the Safe and Environmentally Sound Recycling of Ships, 2009<sup>[5]</sup>.

#### 2 Terms and definitions

For the purposes of this document, the following terms and definitions apply.

#### 2.1

#### iTeh STANDARD PREVIEW asbestos

variety of fibrous silicate minerals, namely actinolite asbestos, amosite, anthophyllite asbestos, chrysotile, crocidolite and tremolite asbestos (standards.iteh.ai)

#### 2.2

#### ISO/PAS 30007:2010

asbestos-containing material https://standards.iteh.ai/catalog/standards/sist/c36cd274-7408-4fc8-a6b6-ACM

material containing more than one percent asbestos or defined material regulated by national rule

#### 2.3

#### clean room

uncontaminated room having facilities for the storage of employees' street clothing and uncontaminated materials and equipment

#### 2.4

#### competent person

person capable of identifying existing asbestos hazards in the workplace and selecting the appropriate control strategy for asbestos exposure and who has the authority to take prompt corrective measures to eliminate them

NOTE The competent person will have appropriate training, certification and/or license that meets the requirements of national legislation for the specific tasks undertaken.

#### 2.5

#### decontamination zone

enclosed area adjacent and connected to asbestos-removal area and consisting of an equipment room (change room), shower area and clean room, which is used for the decontamination of workers, materials, and equipment that are contaminated with asbestos

#### 2.6

#### equipment room

#### change room

contaminated room located within the decontamination zone that is supplied with impermeable bags or containers for the disposal of contaminated protective clothing and equipment

#### 2.7

### high-efficiency particulate air filter

HEPA filter

filter capable of trapping and retaining around at least 99,97 % of all mono-dispersed particles of 0,3  $\mu m$  in diameter

#### 2.8

#### ship recycling

activity of complete or partial dismantling of a ship at a ship recycling facility in order to recover components and materials for reprocessing and reuse or for disposal, including processing hazardous and other materials, and their associated operations such as storage and treatment of components and materials on site, but not their further processing or disposal in separate facilities

#### 2.9

#### inventory

inventory of hazardous materials

NOTE The inventory is a requirement for recycling ships that is specified by *The Hong Kong International Convention for the Safe and Environmentally Sound Recycling of Ships*, 2009.

[ISO/PAS 30006:2010, definition 3.2]

#### 2.10

#### wetting agent

water, or water to which surfactant has been added (to increase the ability of the liquid to penetrate), that is applied to ACM to suppress dust emission during removal

### iTeh STANDARD PREVIEW

# 3 Work categorization (grade) to minimize asbestos emissions and exposure during ship recycling

#### ISO/PAS 30007:2010

In order to minimize the generation of asbestos dust and potential worker exposure during ship recycling operations, the ship recycling facility's competent person shall determine the appropriate work grade in accordance with Table 1, and shall determine corresponding working procedures in accordance with the methodologies given in Table 2.

Since the difficulty of performing a task can be estimated by the type and manner of use of ACM, three work grades have been established accordingly. See Table 1.

Work grade	Description
1	Work for removal of sprayed-on asbestos, which requires strict measures to minimize emission of asbestos to environment and exposure of worker to asbestos such as thermal system insulation or surfacing ACM
2	Work for removal of ACM except sprayed-on asbestos for thermal insulation for main and auxiliary engines, thermal insulation for other pipes and armouring materials subjected to heat
3	Work for removal of ACM except sprayed-on asbestos used in accommodation and service spaces; walls (ceilings, floorings and linings) and moulded seal materials for devices or piping (joint sheets, gaskets, gland packing, packing and linings) <sup>a</sup>

#### Table 1 — Work grading

As factors such as workload, the working environment, and methodologies may vary, the competent person shall periodically review tasks for asbestos abatement both before and during operations to determine if the work grade should be amended.

The user shall ensure compliance with the national requirements.

a When ACM is cut by power-tool, the work shall be categorized in work grade 2.

### 4 Preliminary check for asbestos-containing materials

In order to determine whether asbestos is used in the ship on which work is to be performed, the competent person shall check

- the inventory, and
- the related documents and diagrams.

Equipment, systems or areas that are specified as free of asbestos need not be handled in the same way as ACMs.

#### 5 Planning removal of ACM

#### 5.1 General

Prior to removal of ACM a written plan in accordance with 5.2 to 5.7 shall be made.

#### 5.2 Operational overview

The operational overview shall specify the title of the operation, work period, details of the operation (separately by area) and layout of work site indicated on the plan of the ship.

The overview shall specify the equipment, system or areas in which ACMs are used (based on the check specified in Clause 4) and the work procedure summary for removal of ACM for each work grade. Additionally, a layout for the removal zone shall be made giving dimensions and the precise location of work sites and decontamination zones (in the case of work grade 1), negative-pressure dust collectors (in the case of work grade 1) and the asbestos-containing waste storage:007:2010

https://standards.iteh.ai/catalog/standards/sist/c36cd274-7408-4fc8-a6b6-The user shall ensure compliance with the national-requirements.0

Regardless of the work grade, removal of asbestos containing material should be conducted, to the maximum extent practicable, prior to the removal of other hazardous materials or deconstruction of the vessel itself.

#### 5.3 Organizational chart for managing asbestos removal

An organizational chart to manage asbestos removal shall be made. Especially when directly engaged in ACM removal operations, the employer should attach the document of authorization to perform ACM removal to the chart if necessary.

Documents showing that workers have completed the necessary training and have undergone medical checkups for the specified operations shall be attached to the organizational chart.

#### 5.4 Operating schedule

For items related to the operating schedule, see the removal procedure specified in Clause 6. The schedule should indicate the number of days required for each operation.

#### 5.5 Removal written plan

The removal written plan shall provide information in accordance with the removal procedure specified in Clause 6, in addition to the information required by 5.5.1 and 5.5.2.

#### 5.5.1 Equipment, tools and protective measures

The written plan shall contain a list of equipment and tools needed for removal.

The list shall specify the types and quantities of personal protective equipment required for each job (or task) performed, including but not limited to respirators and protective clothing.

The manufacturers, product names and quantities of wetting agent shall be specified.

#### 5.5.2 Layout of the decontamination zone

The written plan shall incorporate a layout and structural diagram of the decontamination zone [equipment room (change room), shower area, and clean room] and other illustrations that illustrate operational specifics, such as the location of the negative-pressure dust collector.

#### 5.6 Asbestos monitoring plan

If asbestos monitoring (atmosphere, working environment, water, and soil) is required in accordance with national law, there shall be a written plan to specify measuring cycles, locations, methods and designated persons or organization.

#### 5.7 Waste disposal plan

The waste disposal plan shall specify methods for storage, transport, and final disposal of removed ACM. The plan shall also specify the estimated quantity of the ACM wastes. PREVIEW

## (standards.iteh.ai)

### 6 Work procedures for each work grade

ISO/PAS 30007:2010

6.1 General https://standards.iteh.ai/catalog/standards/sist/c36cd274-7408-4fc8-a6b6-29d8e2c37dff/iso-pas-30007-2010

Operations for each grade shall be performed in accordance with the procedures specified in Table 2. For additional information see 6.2 to 6.4.

#### 6.2 Work grade 1

#### 6.2.1 General

Asbestos removal operations of work grade 1 shall be carried out as specified in 6.2.2 to 6.2.7.

#### 6.2.2 Preparation for work

Preparation of tools, material and equipment shall be conducted in accordance with the asbestos-removal plan specified in Clause 5, before starting the asbestos removal operation.

	Work grade 1	Work grade 2	Work grade 3			
Work plan	Draw up plan for removal of ACM <sup>6</sup>	a				
Competent person	Competent person shall be assigned as supervisor					
Special training	Provide workers with special asbestos training <sup>b</sup>					
Protective equipment	Powered air-purifying respirator or full face piece respirators with particulate filter (solid particle collecting efficiency shall be at least 99,9 %) (if possible, pressure-demand-type combination air-line mask respirator) Protective gloves Protective clothing Protective footwear	Same as for work grade 1, or Half-mask respirators with particulate filter (solid particle collecting efficiency shall be at least 99,0 %) can be used for removal without cutting and breaking asbestos thermal insulations Goggles Protective gloves Protective clothing Protective footwear	Same as for work grade 2, or Half-mask respirators with particulate filter (solid particle collecting efficiency shall be at least 95,0 %) Goggles Protective gloves Working clothing			
Emission prevention	Same as for work grade 2 <b>iTeh STAND</b> (standa <u>ISO/P</u> https://standards.iteh.ai/catalog/s 29d8e2c37d	Install a negative-pressure dust collector (in work site) Set up decontamination zone and the stress of the second of a small project, such the removal of a small section with asbestos insulation, may be worked by using a glove bag without isolation with plastic sheeting	Post signs, e.g. "KEEP OUT — ASBESTOS HAZARD" Use a vacuum cleaner incorporating a HEPA filter. Sealed disposal container for waste.			
During/after work	Same as for work grade 2	Saturate and/or solidify materials with wetting agent (dust suppressants) Evaluate/measure the working environment Place waste in the specified sealed disposal container and store in an interim waste storage area Clean up the work site Dispose of or wash protectors used by workers Create work records and maintain on file	Saturate materials with wetting agent (dust suppressants), if moulded products containing asbestos must be crushed, cut, or ground during removal, wetting agent shall be used. Clean up the work site. Dispose of or wash protectors used by workers Draw up work records and maintain on file.			
Waste disposal						
Remark	To carry out work on piping and m 6.5 shall be taken into consideration	achinery insulated with asbestos ma on.	aterials, the procedure provided in			
a A simplified p	plan can be acceptable for grade 3.					
<sup>b</sup> The training of	The training course is different for each work grade. Refer to 6.2 to 6.4 for the details of training to carry out.					
<sup>C</sup> The physical		ently designed and placed to prevent mig				

#### 6.2.2.1 Establishment of supervising organization of removal of asbestos

- a) Assignment of person responsible The competent person shall be assigned as supervisor.
- Establishment of organization for removal of asbestos The organization for removal of asbestos under the supervision of the competent person shall be established.
- c) The competent person shall ensure the following.
  - The workers are correctly wearing appropriate protective equipment.
  - The dust collectors are working correctly.
  - There is no damage or opening of the isolating sheet.
  - The air pressure of the asbestos-removal area is negative relative to the outside air pressure.
  - The workers have received relevant education and training and have had an appropriate medical evaluation.
  - The equipment and work area are monitored at appropriate intervals to ensure that the work environment and procedures, as described above, remain satisfactory.

### 6.2.2.2 Preliminary education and training for workers

In the case that workers have not received education and training specific to asbestos, such training shall be carried out prior to commencing asbestos removal work.

The contents of the education and training specific to asbestos include 274-7408-4fc8-a6b6-29d8e2c37dff/iso-pas-30007-2010

- awareness of the harmful effects of asbestos,
- methods of suppressing scattering of asbestos particles,
- methods of use of protective equipment and training on wearing them,
- emergency procedures,
- regulations concerned, and
- methods of handling waste.

The level of training and education received shall be commensurate with the job duties of the worker.

All workers shall be trained in a language that they understand.

An examination should be conducted to ensure that workers have effectively understood and retained the training.

#### 6.2.2.3 Preparations for protective equipment

Appropriate protective equipment shall be provided.

Respiratory protective equipment shall be powered air-purifying respirator or full face piece respirators with particulate filter (solid particle collecting efficiency shall be at least 99,9%), and pressure-demand-type combination air-line mask respirators as much as possible.

Protective clothing, protective gloves and overshoes covering footwear shall be constructed of materials to which asbestos particles do not easily adhere, and shall be disposable.

Protective footwear should be of a type that is easily decontaminated.

It is necessary to seal with tape any gaps between the respirators and clothing, between gloves and clothing, and between overshoes and clothing.

Protective clothing should be of Type 5 (ISO 13982-1) or equivalent.

Powered air purifying respirators should be compliant with EN 12941 or equivalent.

#### 6.2.2.4 Preparation and installation of equipment to prevent scattering

#### 6.2.2.4.1 Isolation

Prepare work area by removing all non-fixed items before starting work.

The area for removal of asbestos shall be isolated by isolating sheet or any other physical barrier to prevent asbestos from leaking to the outside. The floor of the area shall be covered with a double layer of the isolating sheet and wall and ceiling of the area shall be covered with a single layer of the isolating sheet. The joints of the isolating sheet shall be tightly closed in order not to allow asbestos to migrate from the joint. The isolating sheet shall be impermeable and have sufficient strength, and shall not be easily damaged or broken.

Integrity of isolated area needs to be checked DARD PREVIEW

A small project, such as the removal of a small section with asbestos insulation, may be worked by using a glove bag without isolation with plastic sheeting.

### 6.2.2.4.2 Establishment of decontamination zone

https://standards.iteh.ai/catalog/standards/sist/c36cd274-7408-4fc8-a6b6-

The decontamination zone shall be established adjacent and connected to asbestos-removal area.

Install extraction ventilation in decontamination zone with air flow direction from clean room to equipment room.

An equipment room (change room) shall be supplied with impermeable bags or containers for the disposal of contaminated protective clothing and equipment.

A shower area shall have water shower or air shower.

The clean room shall have facilities for the storage of employees' street clothing and uncontaminated materials and equipment. It is, typically, also adjacent and connected to the decontamination zone.

#### 6.2.2.4.3 Installation of negative-pressure dust collector

The negative-pressure dust collector shall be installed in order that the asbestos-removal area be kept at negative atmospheric pressure relative to the outside and to reduce the concentration of asbestos particles in the asbestos-removal area. The dust collector shall be able to ventilate the working area volume at least four times per hour or at a rate in accordance with national regulations applicable to asbestos-removal area. The dust collector shall be dwell of air inside the asbestos-removal area.

The dust collector shall be able to collect more than 99,97 % of asbestos particles and be equipped with a HEPA filter.

The opening of the suction duct of the dust collector used for asbestos-removal area should be located away from the (outside) air-intake opening in order to prevent contaminated air inside the asbestos-removal area.