



SLOVENSKI STANDARD
oSIST prEN ISO 19901-5:2020
01-junij-2020

Industrija za predelavo nafte in zemeljskega plina - Posebne zahteve za naftne ploščadi - 5. del: Upravljanje teže (ISO/DIS 19901-5:2020)

Petroleum and natural gas industries - Specific requirements for offshore structures - Part 5: Weight management (ISO/DIS 19901-5:2020)

Erdöl- und Erdgasindustrie - Besondere Anforderungen an Offshore Bauwerke - Teil 5: Gewichtskontrolle während der Auslegung und Konstruktion (ISO/DIS 19901-5:2020)

Industries du pétrole et du gaz naturel - Exigences spécifiques relatives aux structures en mer - Partie 5: Contrôle des poids (ISO/DIS 19901-5:2020)

<https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-016682db4b67/osist-pr-en-iso-19901-5-2020>

Ta slovenski standard je istoveten z: prEN ISO 19901-5

ICS:

75.180.10	Oprema za raziskovanje, vrtanje in odkopavanje	Exploratory, drilling and extraction equipment
-----------	--	--

oSIST prEN ISO 19901-5:2020

en,fr,de

iTeh STANDARD PREVIEW
(standards.iteh.ai)

[oSIST prEN ISO 19901-5:2020](https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020)

<https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020>

DRAFT INTERNATIONAL STANDARD

ISO/DIS 19901-5

ISO/TC 67/SC 7

Secretariat: BSI

Voting begins on:
2020-03-23Voting terminates on:
2020-06-15

Petroleum and natural gas industries — Specific requirements for offshore structures —

Part 5: Weight management

*Industries du pétrole et du gaz naturel — Exigences spécifiques relatives aux structures en mer —
Partie 5: Contrôle des poids*

ICS: 75.180.10

iTeh STANDARD PREVIEW (standards.iteh.ai)

[oSIST prEN ISO 19901-5:2020](https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020)<https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020>

THIS DOCUMENT IS A DRAFT CIRCULATED FOR COMMENT AND APPROVAL. IT IS THEREFORE SUBJECT TO CHANGE AND MAY NOT BE REFERRED TO AS AN INTERNATIONAL STANDARD UNTIL PUBLISHED AS SUCH.

IN ADDITION TO THEIR EVALUATION AS BEING ACCEPTABLE FOR INDUSTRIAL, TECHNOLOGICAL, COMMERCIAL AND USER PURPOSES, DRAFT INTERNATIONAL STANDARDS MAY ON OCCASION HAVE TO BE CONSIDERED IN THE LIGHT OF THEIR POTENTIAL TO BECOME STANDARDS TO WHICH REFERENCE MAY BE MADE IN NATIONAL REGULATIONS.

RECIPIENTS OF THIS DRAFT ARE INVITED TO SUBMIT, WITH THEIR COMMENTS, NOTIFICATION OF ANY RELEVANT PATENT RIGHTS OF WHICH THEY ARE AWARE AND TO PROVIDE SUPPORTING DOCUMENTATION.

This document is circulated as received from the committee secretariat.

ISO/CEN PARALLEL PROCESSING



Reference number
ISO/DIS 19901-5:2020(E)

© ISO 2020

iTeh STANDARD PREVIEW (standards.iteh.ai)

[oSIST prEN ISO 19901-5:2020](https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020)

<https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020>



COPYRIGHT PROTECTED DOCUMENT

© ISO 2020

All rights reserved. Unless otherwise specified, or required in the context of its implementation, no part of this publication may be reproduced or utilized otherwise in any form or by any means, electronic or mechanical, including photocopying, or posting on the internet or an intranet, without prior written permission. Permission can be requested from either ISO at the address below or ISO's member body in the country of the requester.

ISO copyright office
CP 401 • Ch. de Blandonnet 8
CH-1214 Vernier, Geneva
Phone: +41 22 749 01 11
Fax: +41 22 749 09 47
Email: copyright@iso.org
Website: www.iso.org

Published in Switzerland

Contents

	Page
Foreword	vi
Introduction	viii
1 Scope	1
2 Normative references	1
3 Terms and definitions	2
4 Abbreviated terms	8
5 Principles of Weight Management	8
5.1 Weight management during project lifecycle phases.....	8
5.2 Objectives.....	9
5.3 Weight development graph.....	10
5.4 Loading conditions.....	12
6 Weight budget	13
6.1 General.....	13
6.2 Requirements.....	13
6.3 Content.....	14
6.3.1 General.....	14
6.3.2 Weight reserves.....	14
6.3.3 Future weights.....	14
6.3.4 Loading conditions and parameters.....	14
6.3.5 Formats and levels.....	15
6.3.6 CoG envelopes.....	15
7 Weight management during project execution phases	15
7.1 Conceptual design.....	15
7.1.1 General.....	15
7.1.2 Estimating principles.....	16
7.1.3 Deliverables.....	17
7.2 FEED.....	17
7.2.1 General.....	17
7.2.2 Weight management Procedure.....	17
7.2.3 Estimating principles.....	18
7.2.4 Weight budget.....	18
7.2.5 Deliverables.....	18
7.3 Detail engineering.....	19
7.3.1 General.....	19
7.3.2 Weight management procedure.....	19
7.3.3 Weight Budget.....	20
7.3.4 Deliverables.....	20
7.4 Construction.....	22
7.4.1 General.....	22
7.4.2 Weight management procedure.....	22
7.4.3 Deliverables.....	22
7.5 Installation.....	22
7.5.1 General.....	22
7.5.2 Weight management procedure.....	23
7.5.3 Deliverables.....	23
7.6 Operating.....	23
7.6.1 General.....	23
7.6.2 Weight management Procedure.....	23
7.7 Decommissioning.....	24
8 Requirements for “as-built” weight documentation	24

ISO/DIS 19901-5:2020(E)

9	Requirements for suppliers' weight data and weighing of equipment and assembled bulks	25
9.1	General	25
9.2	Submission of weight data	25
9.3	Weighing requirements	26
9.3.1	Equipment	26
9.3.2	Bulk	26
9.4	Weighing procedure	26
9.5	Weighing devices	27
9.5.1	Type of weighing device	27
9.5.2	Calibration of weighing devices	27
9.5.3	Maximum relative uncertainty for weighing devices	27
9.5.4	Capacity of weighing device	28
9.5.5	Spare weighing devices and ancillaries	28
9.6	Notification and witnessing of weighing	28
9.7	Scheduling of weighings	28
9.8	Environmental conditions during a weighing	28
9.9	Weighing operation	28
9.10	Temporary objects present during a weighing	29
9.11	Permanent items not installed during a weighing	29
9.12	Weighing Certificate	29
10	Requirements for weighing of major assemblies	30
10.1	General	30
10.2	Weighing procedure	30
10.3	Weighing system	32
10.3.1	Load cells	32
10.3.2	Read-out devices	32
10.3.3	Uncertainty of weighing system	32
10.3.4	Calibration of load cells	32
10.3.5	Capacity of weighing system components	33
10.3.6	Spare load cells and ancillaries	33
10.3.7	Hydraulic jacking system	33
10.3.8	Levelness of the assembly during the weighing	34
10.4	Preparations prior to the weighing	34
10.4.1	Notification and witnessing of weighings	34
10.4.2	Environmental conditions during a weighing	34
10.4.3	Weighing prediction report	34
10.4.4	Temporary items during the weighing	35
10.5	Weighing operation	35
10.5.1	Number of results recorded	35
10.5.2	Readings of load cells and level criteria	35
10.5.3	Consistency of results	36
10.5.4	CoG calculations	36
10.5.5	Weighing certificate	36
10.5.6	Weighing report	36
	Annex A (informative) Weighing certificates	38
	Annex B (normative) Accuracy of major assemblies weighing predictions	42
	Annex C (informative) Example weight budget (WB) summary	43
	Annex D (informative) Guidelines for displacement measurement of floating facilities	44
	Annex E (informative) Weight management during operations	48
	Annex F (informative) Requirements for topside weight estimation — new builds/green field	51
	Annex G (informative) Executive summary description	54
	Annex H (informative) Weighing result uncertainty	57

Annex I (informative) Weight management database structure	60
Annex J (informative) Weight management of concrete structures	61
Annex K (informative) Coordinate systems	64
Bibliography	66

iTeh STANDARD PREVIEW
(standards.iteh.ai)

[oSIST prEN ISO 19901-5:2020](https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020)

<https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020>

ISO/DIS 19901-5:2020(E)

Foreword

ISO (the International Organization for Standardization) is a worldwide federation of national standards bodies (ISO member bodies). The work of preparing International Standards is normally carried out through ISO technical committees. Each member body interested in a subject for which a technical committee has been established has the right to be represented on that committee. International organizations, governmental and non-governmental, in liaison with ISO, also take part in the work. ISO collaborates closely with the International Electrotechnical Commission (IEC) on all matters of electrotechnical standardization.

The procedures used to develop this document and those intended for its further maintenance are described in the ISO/IEC Directives, Part 1. In particular, the different approval criteria needed for the different types of ISO documents should be noted. This document was drafted in accordance with the editorial rules of the ISO/IEC Directives, Part 2 (see www.iso.org/directives).

Attention is drawn to the possibility that some of the elements of this document may be the subject of patent rights. ISO shall not be held responsible for identifying any or all such patent rights. Details of any patent rights identified during the development of the document will be in the Introduction and/or on the ISO list of patent declarations received (see www.iso.org/patents).

Any trade name used in this document is information given for the convenience of users and does not constitute an endorsement.

For an explanation of the voluntary nature of standards, the meaning of ISO specific terms and expressions related to conformity assessment, as well as information about ISO's adherence to the World Trade Organization (WTO) principles in the Technical Barriers to Trade (TBT), see www.iso.org/iso/foreword.html.

This document was prepared by Technical Committee ISO/TC 67, *Materials, equipment and offshore structures for petroleum, petrochemical and natural gas industries*, Subcommittee SC 7, *Offshore structures*.

This third edition cancels and replaces the second edition (ISO 19901-5:2016), which has been technically revised.

The main changes compared to the previous edition are as follows:

- Title changed to Weight Management
- Document restructured and columnisation removed.
- Weight control classes removed
- Requirements for weight management for all project phases implemented
- Annexes restructured:
 - Previous [Annexes A](#) and [B](#) joined into a new [Annex A](#).
 - Previous [Annex B](#) deleted and replaced with new [Annex B](#) Accuracy of major assemblies weighing predictions added
 - Previous [Annex D](#) and [F](#) joined into new [Annex D](#) Guidelines for displacement measurement of floating facilities
 - Previous [Annex E](#) deleted and replaced by new revised [Annex E](#) Weight management during operations
 - Previous [Annex F](#) updated to [Annex D](#) Guidelines for displacement measurement of floating facilities
 - Previous [Annex G](#) updated to [Annex E](#) Weight management during operations

- Previous [Annex H](#) updated to [Annex F](#) Requirements for topside weight estimation — New builds/green field
- Previous [Annex I](#) updated to [Annex G](#) Executive summary description
- Previous [Annex J](#) expanded and updated to [Annex H](#) Weighing result uncertainty
- Previous [Annex K](#) updated to [Annex I](#) Weight management database structure
- New annexes added:
 - [Annex J](#) Weight management of concrete structures
 - [Annex K](#) Coordinate systems

A list of all parts in the ISO 19901 series can be found on the ISO website.

Any feedback or questions on this document should be directed to the user's national standards body. A complete listing of these bodies can be found at www.iso.org/members.html.

iTeh STANDARD PREVIEW (standards.iteh.ai)

[oSIST prEN ISO 19901-5:2020](#)

<https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020>

ISO/DIS 19901-5:2020(E)**Introduction**

The International Standards ISO 19900, ISO 19901 (all parts), ISO 19902, ISO 19903, ISO 19904, ISO 19905 (all parts) and ISO 19906 relating to offshore structures constitute a common basis covering those aspects that address design requirements and assessments of all offshore structures used by the petroleum and natural gas industries worldwide. Through their application the intention is to achieve reliability levels appropriate for manned and unmanned offshore structures, whatever the type of structure and the nature of the materials used.

It is important to recognize that structural integrity is an overall concept comprising models for describing actions, structural analyses, design rules, safety elements, workmanship, quality control procedures and national requirements, all of which are mutually dependent. The modification of one aspect of design in isolation can disturb the balance of reliability inherent in the overall concept or structural system. The implications involved in modifications, therefore, need to be considered in relation to the overall reliability of all offshore structural systems.

ISO 19900, ISO 19901 (all parts), ISO 19902, ISO 19903, ISO 19904, ISO 19905 (all parts) and ISO 19906 relating to offshore structures are intended to provide a wide latitude in the choice of structural configurations, materials and techniques without hindering innovation. Sound engineering judgement is therefore necessary in the use of these International Standards.

**iTeh STANDARD PREVIEW
(standards.iteh.ai)**

[oSIST prEN ISO 19901-5:2020](https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020)

<https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020>

Petroleum and natural gas industries — Specific requirements for offshore structures —

Part 5: Weight management

1 Scope

This document specifies requirements for managing and controlling the weight and centre of gravity (CoG) of offshore facilities by means of mass management during all lifecycle phases; including conceptual design, front end engineering, detail engineering, onshore/inshore construction, and offshore installation. These facilities can be completely new installations (Greenfield) or the modifications to existing installations (Brownfield). It is also necessary to continue managing and controlling weight throughout operations, decommissioning and removal to facilitate Structural Integrity Management (SIM) and to assist with removal of facilities during decommissioning. The provisions are applicable to offshore facilities of all types (fixed and floating). Only items with mass shall be addressed. Loads not related to mass shall be omitted. See ISO 19904-1, ISO 19901-6 and ISO 19901-7.

Weights from mass of snow and ice are not to be included as they are not part of a facility.

This document specifies:

- a) managing and controlling weights and CoGs for components and entire facilities;
- b) managing weight and CoG interfaces;
- c) standardised terminology for weight and CoG estimating and reporting;
- d) requirements for determining Not To Exceed (NTE) weights and budget weights;
- e) weighing and determination of weight and CoG of tagged equipment, major assemblies, modules and facilities;

This document can be used as a basis for:

- a) costing, scheduling or determining suitable construction method(s) or location(s);
- b) planning, evaluating and presenting the client's, contractor's or fabricator's weight management and reporting system;
- c) as a contract reference between client, contractor and suppliers;
- d) as a means of refining the structural analysis or model.

2 Normative references

The following documents are referred to in the text in such a way that some or all of their content constitutes requirements of this document. For dated references, only the edition cited applies. For undated references, the latest edition of the referenced document (including any amendments) applies.

ISO/IEC Guide 98-3, *Uncertainty of measurement — Part 3: Guide to the expression of uncertainty in measurement (GUM:1995)*

ISO/DIS 19901-5:2020(E)

3 Terms and definitions

For the purposes of this document, the following terms and definitions apply.

- 3.1 approved variations**
approved scope changes affecting the predicted weight and changing the weight budget figures.
- 3.2 assembly**
designed and fabricated group of bulk and equipment items which form one unit
- 3.3 brownfield**
modifications/upgrade to an existing installation, including removing of redundant systems and equipment and adding new structures and systems
- 3.4 budget weight**
localised budgets weights and CoG (3.9) parameters set by project for discipline(s) and/or sub-contractor(s) and identified in the weight budget document (3.57)
- 3.5 bulk**
loose construction materials e.g. piping, valves, cable and trays, etc.
EXAMPLE Structural steel also fits the definition of 'bulks'
Note 1 to entry: Bulk items support the equipment items by providing infrastructure around and between them.
- 3.6 centre of gravity CoG**
the point in a body or system of bodies at which the entire weight may be considered to act
Note 1 to entry: For assemblies, modules or facilities, the aggregate CoG is the mathematical weighted average of the CoGs of the individual items (comprising the completed assembly, module or facilities) measured from a common reference point.
- 3.7 client**
organisation for which a weight report is prepared
Note 1 to entry: This is the project owner (oil company/operator, fabricator, engineering sub-contractor, lift/transport contractor, etc.).
- 3.8 contractor**
organisation tasked with the design of a facility or part of a facility.
- 3.9 CoG envelope**
defined constraint volume within which the CoG of an assembly shall remain for a specified loading condition
- 3.10 conceptual design**
the first phase of design, during which several concepts are evaluated until it is clear which concept should be carried forward.

3.11**conceptual design weight allowance**

and allowance added to the conceptual predicted weight to reach the design weight

3.12**consumables**

materials consumed and replenished during normal operating of an offshore installation.

EXAMPLE Potable/service water, diesel fuel, crew provisions, drilling powders for creation of mud and/or cement.

3.13**contents**

fluids or powders held within piping, equipment or structural tanks at their normal operating levels

Note 1 to entry: Typical contents are hydrocarbons, cooling and heating mediums, chemicals, fuels, condensates, seawater, fresh water, powders (drilling cement and mud additives), etc. Fluids continuously installed in an item of equipment (e.g. coolants and lubricating oils) are not to be considered as contents. See dry weight (3.18) for additional explanation.

3.14**deadweight**

total carrying capacity of a floating facility

Note 1 to entry: Includes weight of crude oil, deck cargo, temporary items, water, marine growth, ballast water, consumables, crew and their effects.

Note 2 to entry: See [Annex D](#).

3.15**design weight**

the weight unlikely to be exceeded in conceptual design. This weight is used for engineering purposes

3.16**discipline**

branch of engineering reflecting a single aspect in the project

EXAMPLE Architectural, drilling, electrical, HVAC, instrumentation, loss control (safety), piping, structural and telecommunications.

3.17**displacement**

weight of the volume of water displaced by a floating structure

Note 1 to entry: The sum of lightweight and deadweight including mooring system load, appendences and/or appurtenances e.g. structures outside the moulded hull.

Note 2 to entry: See [Annex D](#).

3.18**dry weight**

weight of a component, weight item or an assembly in its dry installed condition including permanent utilities in closed equipment systems

Note 1 to entry: Examples of permanent utilities are gearbox oil, hydraulic oil, filter sand, coolant, etc.

Note 2 to entry: Any content of operating fluid flowing through a component, weight item or an assembly is excluded.

ISO/DIS 19901-5:2020(E)**3.19
equipment**

component or arrangement of components, built for specific function(s)

Note 1 to entry: The component/assembly normally has unique documentation due to its function and complexity.

Note 2 to entry: Refer to tagged equipment ([3.50](#)) for further explanation.

**3.20
estimate to complete
ETC**

the estimated weight of items not included in the gross WTO in order to bring it up to the predicted weight.

**3.21
estimated weight**

weight based on initial calculation or previous experience

**3.22
fabricator**

organisation contractually tasked with construction of a portion (such as assemblies, modules, topsides, hull etc.) of a facility

**3.23
facility**

a construction (such as a topside, hull etc.) that is built, installed, or established to serve a particular purpose

iTeh STANDARD PREVIEW
(standards.iteh.ai)

**3.24
float-out**

loading condition for transfer of assembly, module or topsides from a construction site to become self-floating

<https://standards.iteh.ai/catalog/standards/sist/3adf93cb-cd4d-467c-a39e-916682db4b67/osist-pren-iso-19901-5-2020>

**3.25
future weight**

weight of a component or an assembly to be installed after a specified time after the start of production

**3.26
front end engineering design
FEED**

the phase following conceptual design phase, during which the selected concept is matured, and design parameters normally are fixed

**3.27
greenfield**

new facilities which are fabricated onshore and installed offshore

**3.28
grillage**

structure, secured to the deck of a transport barge or vessel, designed to support the cargo (e.g. module or topsides) and distribute the loads between the cargo and the internal structure of the transport barge or vessel

**3.29
gross weight take off
gross WTO**

the net weight take off including weight allowance ([3.56](#))

**3.30
hook-up**

installation of components or assemblies after the modules have been installed to complete it into a functioning installation

3.31**lifting gear**

items needed during a lifting operation to connect the lifting hook to the item being lifted

EXAMPLE Slings, spreader bars, lifting frames, shackles.

3.32**lift weight**

weight of a component, assembly, or a module at its lift points, including permanent and temporary items, but excluding the lifting gear

3.33**loading condition**

design condition(s) for which the weight and CoG of an assembly, module or topside is required to be controlled

EXAMPLE Dry, operating, lift, load-out, shackles.

3.34**load-out**

loading condition for transfer by way of horizontal movement of an assembly, module or topsides from its land-based construction site onto a transport barge or vessel

Note 1 to entry: See [5.4](#)

3.35**management reserves**

reserves to take account for any scope changes during the detail engineering phase

3.36**master equipment list****MEL**

project specific list for compiling and management of technical data for tagged equipment

3.37**mating**

loading condition for transfer of an assembly, module or topsides supported on barge(s) or vessel(s) to a temporary or permanent support structure

3.38**module**

assembly of items forming a major building block that forms a component part of a facility, which needs to be controlled with respect to weight and CoG

3.39**net weight take off****net WTO**

the weight take off based on the actual designed data from 3-dimensional model, engineering drawings or supplier data

3.40**not-to-exceed weight****NTE weight**

maximum acceptable weight and CoG envelope for any given loading condition

3.41**operating**

loading condition for an operating offshore facility at the start of steady-state production

Note 1 to entry: All bulk and equipment items are present with contents at nominal operating levels.