TECHNICAL SPECIFICATION

First edition 2017-09

Escalators and moving walks —

Part 6: Safety parameters meeting the GESRs

Escaliers mécaniques et trottoirs roulants —

Partie 6: Titre manque

https://standards.iteh.ai

ISO/TS 8103-6:2017

https://standards.iteh.ai/catalog/standards/iso/13c68319-f5cd-4820-a555-d5e2d047b40a/iso-ts-8103-6-2017



Reference number ISO/TS 8103-6:2017(E)

iTeh Standards (https://standards.iteh.ai) Document Preview

ISO/TS 8103-6:2017

https://standards.iteh.ai/catalog/standards/iso/13c68319-f5cd-4820-a555-d5e2d047b40a/iso-ts-8103-6-2017



© ISO 2017, Published in Switzerland

All rights reserved. Unless otherwise specified, no part of this publication may be reproduced or utilized otherwise in any form or by any means, electronic or mechanical, including photocopying, or posting on the internet or an intranet, without prior written permission. Permission can be requested from either ISO at the address below or ISO's member body in the country of the requester.

ISO copyright office Ch. de Blandonnet 8 • CP 401 CH-1214 Vernier, Geneva, Switzerland Tel. +41 22 749 01 11 Fax +41 22 749 09 47 copyright@iso.org www.iso.org

Page

Contents

Fore	reword	iv
Intro	roduction	v
1	Scope	
2	Normative references	
3	Terms and definitions	
4	Development of global safety parameters (GSPs)4.1Purpose of GSPs4.2Approach	
5	Understanding and implementing GSPs5.1Overall objective5.2Properties and use of GSPs5.2.1GSPs5.2.2Process of implementing GSPs]5.2.3Ways of using GESRs and GSPs5.2.4Applicability of GESRs and GSPs5.2.5Safety objectives of GSPs5.3Use of ISO/TS 25740-1 and this document	7 8 8 8 9 9 9 9 10
6	Global safety parameters	
Ann	nex A (informative) Anthropometric and design data summary	
Ann	nex B (normative) Figures	36
Bibl	oliography Document Preview	

ISO/TS 8103-6:2017

https://standards.iteh.ai/catalog/standards/iso/13c68319-f5cd-4820-a555-d5e2d047b40a/iso-ts-8103-6-2017

Foreword

ISO (the International Organization for Standardization) is a worldwide federation of national standards bodies (ISO member bodies). The work of preparing International Standards is normally carried out through ISO technical committees. Each member body interested in a subject for which a technical committee has been established has the right to be represented on that committee. International organizations, governmental and non-governmental, in liaison with ISO, also take part in the work. ISO collaborates closely with the International Electrotechnical Commission (IEC) on all matters of electrotechnical standardization.

The procedures used to develop this document and those intended for its further maintenance are described in the ISO/IEC Directives, Part 1. In particular the different approval criteria needed for the different types of ISO documents should be noted. This document was drafted in accordance with the editorial rules of the ISO/IEC Directives, Part 2 (see www.iso.org/directives).

Attention is drawn to the possibility that some of the elements of this document may be the subject of patent rights. ISO shall not be held responsible for identifying any or all such patent rights. Details of any patent rights identified during the development of the document will be in the Introduction and/or on the ISO list of patent declarations received (see www.iso.org/patents).

Any trade name used in this document is information given for the convenience of users and does not constitute an endorsement.

For an explanation on the voluntary nature of standards, the meaning of ISO specific terms and expressions related to conformity assessment, as well as information about ISO's adherence to the World Trade Organization (WTO) principles in the Technical Barriers to Trade (TBT) see the following URL: www.iso.org/iso/foreword.html.

This document was prepared by Technical Committee ISO/TC 178, *Lifts, escalators and moving walks*...

A list of all parts in the ISO 8103 series can be found on the ISO website.

<u>ISO/TS 8103-6:2017</u>

https://standards.iteh.ai/catalog/standards/iso/13c68319-f5cd-4820-a555-d5e2d047b40a/iso-ts-8103-6-2017

Introduction

This document was prepared under the old numbering of the ISO 25740 series. With the resolution of the plenary Meeting in Sydney 09/2016, the new number of this document will be ISO/TS 8103-6. When the renumbering of the standards to 810x-family is finished, this document is revised.

This document was prepared in response to the need to set global safety parameters for escalators and moving walks.

The objective of ISO/TS 25740-1 and this document is to:

- a) define a common global level of safety for all people using, or associated with escalators and moving walks;
- b) facilitate innovation of escalators and moving walks not designed according to existing local, national or regional safety standards, while maintaining equivalent levels of safety. If such innovations become state of the art, they can then be integrated into the detailed local safety standard, at a later date; and
- c) help remove trade barriers.

ISO/TS 25740-1 establishes global essential safety requirements (GESRs) for escalators and moving walks by addressing hazards and risks that can be encountered on escalators and moving walks. The GESRs however, state only safety objectives of escalators and moving walks.

This document provides guidance and criteria for achieving conformance with safety requirements of GESRs by specifying global safety parameters (GSPs) for use and implementation, where applicable, in an escalator or moving walk to eliminate hazards or mitigate safety risks addressed in the GESRs. However, GSPs are not mandatory.

<u>Clause 4</u> describes the approach and methodology used in the development of this document. <u>Clause 5</u> gives instructions for the use and implementation of GSPs. The GSPs are presented in <u>Clause 6</u> in the sequence of GESRs in ISO/TS 25740-1.

https: This document is a product safety standard in accordance with ISO/IEC Guide 51. iso-ts-8103-6-2017

iTeh Standards (https://standards.iteh.ai) Document Preview

ISO/TS 8103-6:2017

https://standards.iteh.ai/catalog/standards/iso/13c68319-f5cd-4820-a555-d5e2d047b40a/iso-ts-8103-6-2017

Escalators and moving walks —

Part 6: Safety parameters meeting the GESRs

1 Scope

This document:

- a) specifies global safety parameters (GSPs) for escalators and moving walks, their components and their functions;
- b) complements the system and methods specified in ISO/TS 25740-1 for mitigating safety risks that can arise in the course of, the operation and use of, or work on, escalators and moving walks.

This document is applicable to escalators and moving walks that can:

- a) be located in any permanent and fixed structure within or attached to a building;
- b) have any
 - 1) rated load, size of load carrying unit and speed, and
 - 2) travel height: https://standards.iteh.ai)
- c) be affected by fire and weather; ment Preview
- d) be foreseeably misused, but not vandalized.

This document does not specifically cover

- s://standards.iteh.a/catalog/standards/iso/13c68319-f5cd-4820-a555-d5e2d047b40a/iso-ts-8103-6-2017
 - needs of users with disabilities, and
 - risks arising from
 - work on escalators and moving walks under construction or during alterations and dismantling;
 - vandalism, and
 - fire in the environment of the escalator or moving walk.

2 Normative references

The following documents are referred to in the text in such a way that some or all of their content constitutes requirements of this document. For dated references, only the edition cited applies. For undated references, the latest edition of the referenced document (including any amendments) applies.

ISO 14798:2009, Lifts (elevators), escalators and moving walks — Risk assessment and reduction methodology

ISO/TS 25740-1:2011, Safety requirements for escalators and moving walks — Part 1: Global essential safety requirements (GESR)

3 Terms and definitions

For the purposes of this document, the following terms and definitions apply.

ISO/TS 8103-6:2017(E)

ISO and IEC maintain terminological databases for use in standardization at the following addresses:

- ISO Online browsing platform: available at http://www.iso.org/obp
- IEC Electropedia: available at http://www.electropedia.org/

3.1

authorized person

person suitably trained with authorization to access restricted areas of *escalators* (3.9) and *moving* walks (3.25) (e.g. machinery spaces, separate machine rooms) and to work there, for the purpose of inspecting, testing and maintaining

[SOURCE: ISO/TS 25740-1:2011, 3.1]

3.2

cause

circumstance, condition, event or action that in a hazardous situation (3.16) contributes to the production of an *effect* (3.6)

[SOURCE: ISO 14798:2009, 2.1]

3.3

competent person

person in possession of the necessary technical knowledge, skills, qualification and experience to perform a work or task

3.4

control

system that governs the starting, acceleration, speed, deceleration and/or stopping of the LCU (3.20)

[SOURCE: ISO/TS 25740-1:2011, 3.3]

3.5

corrective action

action taken to reduce risk (3.30)

[SOURCE: ISO/TS 25740-1:2011, 3.4]

3.6

effect

result of a *cause* (3.2) in the presence of a *hazardous situation* (3.16)

[SOURCE: ISO 14798:2009, 2.2]

3.7

electromagnetic compatibility

EMC

degree of immunity to incident electromagnetic radiation and level of emitted electromagnetic radiation of electrical apparatus

3.8

enclosure of the travel path

structural elements which isolate the travel path from all other areas or space

[SOURCE: ISO/TS 25740-1:2011, 3.12]

3.9

escalator

power-driven, inclined, continuous moving stairway, including guards adjacent to the travel path, used for raising or lowering persons in which the user carrying surface of the LCU (e.g. steps) remains horizontal

[SOURCE: ISO/TS 25740-1:2011, 3.15]

3.10 essential safety requirement ESR

requirement intended to eliminate or sufficiently mitigate the risk (3.30) of harm (3.13) to users (3.41), non-users (3.26), and authorized persons (3.1) using or associated with escalators (3.9) and moving walks (3.25)

3.11 global essential safety requirement GESR

globally agreed upon essential safety requirement

Note 1 to entry: See <u>3.10</u>.

3.12 global safety parameter GSP

globally agreed upon *safety parameter* (3.34)

Note 1 to entry: See 3.34.

3.13 harm

physical injury or damage to the health of people, or damage to property or the environment

[SOURCE: ISO 14798:2009, 2.3]

https: 3:14 dards.iteh.ai/catalog/standards/iso/13c68319-f5cd-4820-a555-d5e2d047b40a/iso-ts-8103-6-2017

harmful event

occurrence in which a *hazardous situation* (3.16) results in *harm* (3.13)

[SOURCE: ISO 14798:2009, 2.4]

3.15

hazard potential source of harm (3.13)

[SOURCE: ISO 14798:2009, 2.5]

3.16

hazardous situation

circumstance in which people, property or the environment are exposed to one or more hazards (3.15)

[SOURCE: ISO 14798:2009, 2.6]

3.17 incident effect

event or occurrence, which can, but does not necessarily create a risk (3.30) of harm (3.13), including risks possible due to, shearing, crushing, falling, impact, trapping, fire, electric shock, exposure to weather, etc.

[SOURCE: ISO/TS 25740-1:2011, 3.13]

3.18

landing

floor, balcony or platform used to receive and discharge persons from the LCU (3.20)

[SOURCE: ISO/TS 25740-1:2011, 3.14]

3.19

life cycle

period of usage of a component or the machinery

[SOURCE: ISO 14798:2009, 2.7]

3.20

load carrying unit

LCU

step/pallet/belt designed to carry persons for the purpose of transportation

[SOURCE: ISO/TS 25740-1:2011, 3.17]

3.21

LCU system

continuous connection of multiple LCUs (3.20) designed to carry persons for the purpose of transportation forming a transportation path

3.22

machinery escalator (3.9) or moving walks (3.25) machine(s) mechanisms and associated equipment

[SOURCE: ISO/TS 25740-1:2011, 3.18] S://standards.iteh.ai)

3.23

Document Preview

space(s) inside or outside of the supporting structure where the machinery as a whole or in parts is placed

3.24

ISO/TS 8103-6:2017

maintenance rds. iteh. a/catalog/standards/iso/13c68319-15cd-4820-a555-d5e2d047b40a/iso-1s-8103-6-2017 process of examination, lubrication, cleaning, adjustments, repair and replacement of parts of *escalators* (3.9) and *moving walks* (3.25) to ensure the safe and intended functioning of escalators and moving walks and its components after the completion of the installation and throughout its *life cycle* (3.19)

3.25

moving walk

machinery space

power-driven installation for the conveyance of persons, including guards adjacent to the travel path, in which the user carrying surface of the LCU (3.20) remains parallel to its direction of motion and is uninterrupted (e.g. pallets, belt)

[SOURCE: ISO/TS 25740-1:2011, 3.16]

3.26

non-user

person in the vicinity of an *escalators* (3.9) or *moving walks* (3.25) but not intending to access or use it

[SOURCE: ISO/TS 25740-1:2011, 3.20]

3.27

protective measures

means used to reduce risk (3.30)

Note 1 to entry: Protective measures include risk reduction by inherently safe design, protective devices, personal protective equipment, information for use and installation, and training.

Note 2 to entry: See also definition for "corrective actions" in <u>3.5</u>.

[SOURCE: ISO 14798:2009, 2.8]

3.28 rated load

load that the *escalator* (3.9) or *moving walks* (3.25) is designed to move

[SOURCE: ISO/TS 25740-1:2011, 3.22]

3.29

relative movement

situation where a component of an *escalator* (3.9) or *moving walks* (3.25) moves in the vicinity of other components of escalators or moving walks that is stationary, or that moves at a different speed or in a different direction; also a situation where a component of an escalator or moving walk moves in the vicinity of a structure where persons may be present

EXAMPLE Building floor surrounding the escalator or moving walk.

3.30

s.su risk

combination of the probability of occurrence of *harm* (3.13) and the *severity* (3.36) of that harm

[SOURCE: ISO 14798:2009, 2.10]

3.31

risk analysis

systematic use of available information to identify *hazards* (3.15) and to estimate the *risk* (3.30)

[SOURCE: ISO 14798:2009, 2.11]

Note 1 to entry: This method aims at systematically identifying and assessing hazards, evaluating risks and recommending risk reduction measures.

3.32

risk assessment

overall process comprising a *risk analysis* (3.31) and a *risk evaluation* (3.33)

ps [SOURCE: ISO 14798:2009, 2.12] [s/iso/13c68319-15cd-4820-a555-d5c2d047b40a/iso-ts-8103-6-2017

3.33

risk evaluation

consideration of the risk analysis (3.31) results to determine if the risk reduction is required

[SOURCE: ISO 14798:2009, 2.13]

3.34 safety parameter SP

quantitative unit, the value of which, in the form of numerical values or references to ISO, IEC or other standards, provides a level of safety consistent with that provided by relevant standards in current use in the *escalator* (3.9) or *moving walks* (3.25) industry and sound engineering practices

3.35

scenario

sequence of a hazardous situation (3.16), cause (3.2) and effect (3.6)

[SOURCE: ISO 14798:2009, 2.14]

3.36

severity

qualitative measure of the worst possible *incident/effect* (3.17) that could be caused by a specific *hazard* (3.15)

[SOURCE: ISO 14798:2009, 2.15]

3.37

sound engineering practice

use of engineering or technical methods to design or evaluate a design or system by taking into account relevant factors that can influence its efficacy and operation

Note 1 to entry: This practice also involves the use of applicable standards, specifications, codes, regulatory and industrial guidelines, as well as accepted engineering and design methods and installation and maintenance practices.

3.38

transportation

process whereby persons step onto a moving LCU (3.20), which then travels from one *landing* (3.18) to another landing, where the person exits the LCU

[SOURCE: ISO/TS 25740-1:2011, 3.29]

3.39

travel path

path and related space within which LCU (3.20) travels between the landing (3.18)

[SOURCE: ISO/TS 25740-1:2011, 3.33]

3.40

uncontrolled movement

situation where

- LCU (3.20) moves when the escalator (3.9) or moving walks (3.25) was to remain stationary, or

LCU travels at a speed that is out of control of the means designed and intended to control the LCU speed during operation.

EXAMPLE 1 LCU starts to move, due to failure of, or breakdown in, escalator or moving walk components, such as speed control, drive or brake system.

EXAMPLE 2 The LCU speed exceeds its designed speed or does not decelerate or stop as intended, due to failure of, or breakdown in, components of an escalator or moving walk, such as speed control, drive or brake system.

[SOURCE: ISO/TS 25740-1:2011, 3.31]

3.41

user

person using the *escalator* (3.9) or *moving walk* (3.25) for the purpose of transportation

[SOURCE: ISO/TS 25740-1:2011, 3.32]

3.42

vandalism

deliberate destruction of or damage to property for no obvious gain or reason

3.43

working area or space

area or space defined for use by *authorized persons* (3.1) to perform maintenance, inspection or testing of an *escalator* (3.9) or *moving walks* (3.25)

[SOURCE: ISO/TS 25740-1:2011, 3.33]